



CASE STUDIES

CLIENT ➔ Bristol Council
SECTOR ➔ Stadia
SERVICES ➔ Resin Flooring
FINISH ➔ Decorative



PROJECT

Performance flooring were appointed to install resin flooring systems to the newly built West Stand at Bristol City FC's Ashton Gate stadium.

The project was awarded following previous successful installation in stadia around the UK including the Olympic stadium.

CHALLENGE

The project had to take place between the off-season for football, however the stadium is a multi-use venue and host Bristol Bears RFC, Bristol Flyers basketball team and also corporate events.

The project programme allowed us 8 days to complete the works and ensure it was fully cured in time for heavy traffic on day 9.

The interesting triangular pattern also meant the works had to be carried out in phases to add more time constraints to the programme.

SOLUTION

Performance flooring installed 3,800m of coatings including crack repairs to the slab. The system used incorporated fine aggregates to ensure slip resistance was maintained when the concourse was wet.

The slab was prepared by diamond grinding, followed by captive shot blasting.

Flowcrete, flowprime was used to seal the concrete, followed by three coats of Flowseal UVR pigmented coating to give the coloured appearance with anti-slip aggregates incorporated in the middle coat.

The finished solution looks excellent and was finished in time for the rugby game on day 9, to the delight of the client.



SALES@PERFORMANCE-FLOORING.CO.UK

+44 (0) 1225 667 897

PERFORMANCE FLOORING, THE GUILD HUB, HIGH ST. BATH. BA1 5EB